



PROJECT: Refurbishment Of Distribution Centre, Lancashire (Phase 2)

PRODUCTS: Refurbishment of 22no Loading Bay Doors
Supply of 22no New Dock Shelters, Pairs of Dock Buffers, Traffic Lights
Supply of 10no Electric Operated Level Access Doors

The second phase of the project involved the refurbishment of distribution centre buildings at another location on the estate.



Our work involved refurbishment of another 22no existing loading bays. Each loading bay door was completely stripped of the damaged/worn panels and replaced with new door panels. External silver finish and with a row of vision panels.



The existing dock shelters & buffers were replaced with 22no new dock shelters and dock buffers.

A total of 10no new openings were constructed to the rear of the building. A&C supplied and fitted 10no new Electric Operated Sectional Overhead Doors 4800mm (W) x 5500mm (H).

MADE IN GREAT BRITAIN

